

Technical Elements of Recommended Storm Drainage Improvements





- Construction of a new headwall downstream of the existing and proposed residential structures
- Construction of a new 1050 mm piped connection through the subject property with SRW as necessary
- Discharge into the existing drainage system and improved ditch along Lower Glenrosa Road

