
# West Kelowna Transmission Project

Rachelle Trent, Project Manager Sabrina Locicero, Stakeholder Engagement




November 2019



# **Agenda**

- Project status
- Existing line
- · Update: Resiliency alternative
- Structured Decision Making
- Next steps



# **West Kelowna Transmission Project**

# West Kelowna Transmission Project Valleyview Substation Fastiand Armstrong 13 Armstrong 13 Substation FortisBC FortisBC

### 3 Timeline | WKTP


### Timeline:

- In February 2015, the project was announced to construct a new, secondary transmission line.
- Spring 2015 to fall 2016, we studied three alternatives.
- Fall 2016, Alternative 2: Westbank Substation to Nicola Substation was identified as the leading alternative for further study.
- Spring to fall 2019, work on new Resiliency Alternative completed.
- Confirm preferred alternative in 2020 at the earliest.

# BC Hydro Power smart

# **The Existing Line**

- The Westbank Substation is supplied by a single radial 138 kV transmission line from Nicola Substation Westbank Substation constructed in 1967.
- Second largest communities in the BC Hydro system supplied by a radial transmission line.
- Serves 22,000 customers in West Kelowna and Peachland.
- 80km in length, 369 structures, 30m wide right-of-way



# **Existing Line Performance**


### **Performance**

In the past 20 years:

- 4 unplanned outages
- 16 total outage hours
- 4 average hours per outage
- 9 hour maximum outage duration

### 2019 Maintenance

- Enhanced access maintenance
- Vegetation removal around poles
- Fire retardant application to wood poles



Performance of the Existing Line | WKTP



# **Resiliency Alternative**

 This alternative looks to improve the resiliency of the existing transmission line to minimize the risk of outages resulting from forest fires and geotechnical events.

### **Studies completed summer 2019**

- Wildfire and geotechnical assessments.
- Environmental overview assessment and archaeological assessment.
- Consultation with First Nations, governments and stakeholders.




Above: Example of an H-frame structure




# **Resiliency**

### Wildfire Risk Assessment

- Considered ignition potential, fire behaviour and suppression capability for a 5km buffer on both sides of existing line over the next 30 to 40 years.
- Two climate scenarios considered:
  - 1. All weather station data from 1970 to 2018
  - 2. Data from only 2000 to 2018:
    - Provincially, 2000 to 2018 wildfire seasons have been more severe resulting in higher severity wildfires and a larger burned area.
- 50% of the line is in high and extreme risk areas for Scenario 1 increasing to 61% for Scenario 2.
- 28% of the line is in low risk areas for Scenario 1,
   22% for Scenario 2.



Overall wildfire risk analysis results for Climate Scenario 1 (above) and 2 (below)




# Resiliency

# Wildfire and Geotechnical Design Mitigation Options

### Considerations include:

- Base protection for wood-poles
- Materials selection: steel or fiberglass poles
- Right-of-way design
- · Access improvements
- Grounding
- Drainage control, protective berms, sour protection and foundation design
- Enhanced design parameters for extreme ice and wind







# **Structured Decision Making**

Higher, Moderate, Lower Ripulmoact

oments from letters teved by BG Hydro

Not Supported Inotherent Supported

sistain and Emarce First

rtain or Entance Reput Stakeholders

 Our work on the new secondary line alternatives and the Resiliency Alternative informs our decision-making

- · Key aspects will include:
  - · First Nations relationships
  - · Environmental risks
  - Reliability
  - Safety
  - · Socio-economic impacts
  - Stakeholders
  - Cost
- The project timeline and in-service date will be updated once a preferred alternative is confirmed.

9 Identifying a Preferred Alternative | WKTP



# **Next Steps**

- Complete the assessment of the Resiliency Alternative by end of 2019.
- Complete the detailed review of the costs for the new line (redundancy) alternatives by end of 2019.
- Anticipate a decision on next steps by early 2020.

