



CITY OF WEST KELOWNA
DEVELOPMENT PERMIT WITH VARIANCES
DP 21-03

TO: E12K Systems Inc. (Inc. No. 729179)
200 – 537 Leon Avenue
Kelowna, BC V1Y 2A9

0746043 BC Ltd.
800 – 1708 Dolphin Avenue
Kelowna, BC V1Y 9S4

0746031 BC Ltd.
800 – 1708 Dolphin Avenue
Kelowna, BC V1Y 9S4

1068059 BC Ltd.
1800 – 1631 Dickson Avenue
Kelowna, BC V1Y 0B5

1. This Permit is issued subject to compliance with all of the Bylaws of the City of West Kelowna applicable thereto, except as specifically varied or supplemented by this Permit.
2. This Permit applies to and only to those lands within the City of West Kelowna described below, and any and all buildings, structures and other developments thereon:

Lot A, District Lot 3478, ODYD, Plan KAP56155, Except Plans KAP56156 and KAP57629 (2802 Smith Creek Road)

3. This Permit allows for the proposed fifty-five (55) lot subdivision consisting of site preparation/grading and construction of fifty-four (54) single family lots and one remainder lot. The application includes a Variance request to vary the front parcel boundary setback on Lots 18 - 20 and 41 - 43 for garage and house from 6.0 m to 3.5 m; and for Lots 44 and 45 for garage from 6.0 m to 4.5 m; and to vary the required minimum parcel frontage for Lots 5 - 14 to allow frontage less than 10% of the perimeter of the parcel. This Hillside, Sensitive Terrestrial Ecosystem and Wildfire Development Permit is subject to the following conditions and related Schedules:
 - a. All construction activities to be conducted on the land in general accordance with Schedule 'A' and the following reports and conditions:
 - i. With the exception of limited grading and restoration works to accommodate the construction of the north side of Smith Creek Road adjacent to the proposed lots, no additional construction activities, road works or on-site servicing is permitted on the proposed remainder lot to the north of Smith Creek Road until such time as a future Development Permit has been issued;
 - ii. 1.2 m high black chain link fencing to be installed as delineated on the red-lined Site Servicing Plan in accordance with Zoning Bylaw No. 0154. Fence construction must either be completed as a condition of final subdivision approval or works agreement with security has been provided;
 - iii. Prior to final subdivision approval, a pull-through access to Aspen Park to be installed as delineated on the red-lined Site Grading Plan, and electrical and water service as delineated on the red-lined Site Servicing Plan, including roll-over curb fronting the park with a compacted gravel surface to allow park maintenance

- vehicles to pull off Smith Creek Road and pull through to exit back onto Smith Creek Road;
- iv. Prior to final subdivision approval, the proposed access to Black Canyon Park through the proposed 4.5 m wide statutory right of way along the back of Lots 18-20 must be constructed in general conformance with the Site Servicing Plan, as a Major Multi-Use Path as per Works and Services Bylaw No. 0249, Drawing No. 105. The access must either be completed or a works agreement with security has been provided as a condition of final subdivision approval;
 - v. In addition to the silt fence and other sediment control works identified on the Erosion & Sediment Control Plan, additional "Gravel Entrance" areas may be required if other access points are created onto Smith Creek Road beyond the identified single entry point at Road A; and additional dust control may be necessary in periods of excessive drought conditions with any earth-moving on or off the site;
 - vi. Geotechnical Investigation, prepared by Calibre Geotechnical Engineering Ltd., dated October 4, 2019; and
 - vii. Prior to final subdivision approval, wildfire mitigation work must be completed to bring fire hazard rating to low to moderate in accordance with the following reports prepared by R.J.P. Holdings Ltd.;
 - a. Wildfire Hazard Assessment and Prescription Report, dated June 6, 2014;
 - b. Wildfire Hazard Assessment and Prescription Report, dated November 19, 2018; and
 - c. Wildfire Hazard Status, dated January 27, 2021.
- b. All restoration and construction activities to be in accordance with Schedule 'B' and the following reports and conditions:
- i. Reports prepared by OKGN EHS Services Ltd.;
 - a. Environmental Management Plan, dated January 25, 2021, including the updated Landscape Plan in Schedule 'B';
 - b. Environmental Impact Assessment Report, dated January 25, 2021;
 - ii. All works within Aspen Park require email notification to the Parks Planner prior to the work being completed, where grading, fencing, hydro-seeding and park access require final approval by the Parks Department;
 - iii. Prior to the completion of any hillside restoration works following completion of site grading, ensure that the proposed covenant and restoration areas have been flagged for review in conjunction with any required legal surveys for the covenant areas;
 - iv. Additional covenant area may be required on proposed Lot 1, which will require additional review following site grading including potential hillside restoration not currently noted on the Landscape Plan or Site Grading Plan;
 - v. Any clearing activities between the active bird breeding/nesting window (April 15 to August 15) will require environmental monitoring every 72 hours
 - vi. Mechanical or hand pulling of weeds must occur each spring (Mar – Jun) and fall (Sep – Nov) to prevent propagation of weeds for a minimum of three (3) years following restoration planting.
- c. Retaining wall construction, design, and finish to be in accordance with Schedule 'C';
- i. Two tier retaining walls along the southern boundary of Lot 17, 18 and 19 in small lock block (Basalite Valley Stone in Tuscany colour finish) to a maximum height of 2.5 m with 2 m separation between the tiers; and
 - ii. A separate Building Permit is required for the retaining walls prior to construction.
- d. That the following variances to City of West Kelowna Zoning Bylaw No. 0154 in accordance with Schedule 'D' be included as part of this Development Permit:
- i. S.10.4.5(g).1 to reduce the front parcel boundary setback:

- a. On Lots 18 – 20 and 41 - 43 for garage or carport having vehicular entry from the front from 6.0 m to 3.5 m; and for house from 4.5 m to 3.5 m, providing that 6.0 m is maintained from garage to laneway or back of curb/sidewalk;
- b. On Lots 44 and 45 for a garage or carport having vehicular entry from the front from 6.0 m to 4.5 m, providing that 6.0 m is maintained from garage to laneway or back of curb/sidewalk; and
- i. That the required minimum frontage for Lots 5 to 15 be varied to allow frontage less than 10% of the perimeter of the parcel as per exemptions permitted by *Local Government Act*, section 512(1), where the required minimum parcel frontage is still greater than the required 16.0 m for the Single Detached Residential (R1) Zone.

Security

- 4. As a condition of the issuance of this permit, the property owner shall deposit 125% of the cost estimate for the landscaping (\$41,500.00 = \$33,200.00 x 125%) as performance security to ensure installation of the required landscape restoration and park grading in accordance with the City's Development Application Procedures Bylaw No. 0260.
- 5. The City of West Kelowna will hold the security outlined above, to ensure that the development is carried out in accordance with this Permit. Should any interest be earned upon the security, it shall accrue to the Permittee and be paid to the Permittee if the security is returned. The condition of the posting of the security is that should the Permittee fail to carry out the development hereby authorized, according to the terms and conditions of the Permit within the time provided, the City of West Kelowna may use the security to carry out the work by its servants, agents or contractors, and any surplus shall be paid over to the Permittee, or should the Permittee carry out the development approved by this Permit, the security shall be returned to the Permittee.
- 6. The landscape (hillside revegetation) and park grading security is refundable upon the receipt of a substantial completion report prepared by the qualified environmental professional or similar qualified professional, and site inspection undertaken by staff. In accordance with the City's Development Applications Procedures Bylaw No. 0260, upon substantial completion, the City will return 90% of the security deposit. The City will withhold the remaining 10% as a maintenance bond for up to three growing seasons to ensure that the work has been fully implemented and demonstrated to function as designed as per the recommended time period in the Environmental Assessment.

General Terms

- 7. The land described herein shall be developed strictly in accordance with the terms and conditions of this Permit and any plans and specifications attached to this Permit, which shall form a part hereof. Should any change be required to this permit, please ensure that you obtain written approval from the City of West Kelowna prior to making any changes.
- 8. If this Development Permit has not been issued within one year from approval, Development Permit with Variances DP 21-03 shall be deemed to have been refused and the file will be closed.
- 9. **This Permit is not a Building Permit.**
- 10. Subject to the terms of the permit, where the holder of a permit issued under the *Local Government Act* does not substantially commence any construction with respect to which the permit was issued within two years after the date it is issued, the permit lapses.

AUTHORIZING RESOLUTION NO. _____ PASSED BY THE MUNICIPAL COUNCIL ON

Signed on _____

City Clerk

As received on _____, there is filed accordingly an Irrevocable Letter of Credit or Bank Draft deposit in the amount of \$41,500.00.

I hereby confirm that I have read and agree with the conditions of Development Permit with Variances DP 21-03 and will ensure that copies of the Permit will be provided to onsite personnel at time of construction.

Signed on _____

Property Owner or Agent

ISSUED on _____

Schedules:

Schedule A:

1. Drawings prepared by Protech Consulting Ltd. (10 pages):
 - a. Lot Layout
 - b. Preliminary Site Grading
 - c. Site Servicing Plan
 - d. Site Grading Cross Sections
 - e. Aspen Park Cross Sections
 - f. Preliminary Road A Plan/Profile drawings
 - g. Preliminary Smith Creek Road Plan/Profile drawings
 - h. Sediment and Erosion Control Plan

Schedule B:

1. Drawings and estimate prepared by The Field Room (4 pages)
 - a. Landscape Plan
 - b. Estimate of Probable Cost

Schedule C:

1. Geotechnical Review of Retaining Walls, prepared by GeoPacific (5 pages)

Schedule D:



1. Development Variance Plan (1 page)

Schedule A





















SINGLE DETACHED RESIDENTIAL ZONE (R1)

| SUBDIVISION REGULATIONS | |
|---------------------------------|---|
| (a) MINIMUM PARCEL AREA | 550 m ² (5,920.2 ft ²) |
| (b) MINIMUM USEABLE PARCEL AREA | 330 m ² (3,552.1 ft ²) |
| (c) MINIMUM PARCEL FRONTAGE | 16.0 m (52.5 ft) |
| DEVELOPMENT REGULATIONS | |
| (d) MAXIMUM DENSITY: | |
| .1 SINGLE DETACHED DWELLING | 1 PER PARCEL |
| (e) MAXIMUM PARCEL COVERAGE | 40% |
| (f) MAXIMUM BUILDING HEIGHT: | 9.0m (29.5 ft) TO A MAXIMUM OF 3 STOREYS EXCEPT IT IS 5.0m (16.4 ft) FOR ACCESSORY BUILDINGS AND STRUCTURES |

| SITING REGULATIONS | |
|---|--|
| (g) BUILDING AND STRUCTURES SHALL BE SITED AT LEAST THE DISTANCE FROM THE FEATURE INDICATED IN THE MIDDLE COLUMN BELOW, THAT IS INDICATED IN THE RIGHT-HAND COLUMN OPPOSITE THAT FEATURE: | |
| .1 FRONT PARCEL BOUNDARY OR PRIVATE ACCESS EASEMENT, WHICHEVER IS CLOSER | 4.5m (14.8 ft) EXCEPT IT IS 6.0m (19.7 ft) FOR A GARAGE OR CARPORT HAVING VEHICULAR ENTRY FROM THE FRONT |
| .2 REAR PARCEL BOUNDARY OR PRIVATE ACCESS EASEMENT, WHICHEVER IS CLOSER | 3.0m (9.8 ft) |
| .3 INTERIOR SIDE PARCEL BOUNDARY | 1.5m (4.9 ft) |
| .4 EXTERIOR SIDE PARCEL BOUNDARY OR PRIVATE ACCESS EASEMENT, WHICHEVER IS CLOSER | 4.5m (14.8 ft) EXCEPT IT IS 6.0m (19.7 ft) FOR A GARAGE OR CARPORT HAVING VEHICULAR ENTRY FROM THE EXTERIOR SIDE |
| .5 A1 ZONE OR ALR | 15.0m (49.2 ft) EXCEPT IT IS 9.0m (24.6 ft) IF A LEVEL 1 BUFFER IS PROVIDED. |

-  - GREATER THAN 40% SLOPES
-  - NO BUILD, NO DISTURB COVENANT AREA



| LEGEND | |
|----------------|---|
| WATER |  |
| SANITARY SEWER |  |
| STORM SEWER |  |
| GAS |  |
| UG TELEPHONE |  |
| UG ELECTRICAL |  |
| MANHOLE |  |
| POWER POLE |  |
| LAMP STANDARD |  |
| CATCH BASIN |  |
| HYDRANT |  |
| TREES |  |
| MH |  |
| P.P. |  |
| L.S. |  |
| C.B. |  |
| I.C. |  |
| C.S. |  |
| LPT |  |
| SERVICE BOX |  |

| | | | | | |
|-----|----------|------|----|---------------------|-------|
| No. | MM/DD/YY | DATE | BY | REVISION | Chk'd |
| 8 | 06/25/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 7 | 06/10/21 | KCL | | ISSUED FOR APPROVAL | KCL |
| 6 | 05/25/21 | TWJM | | ISSUED FOR APPROVAL | KCL |

| | | | | | |
|-----|----------|------|----|----------------------|-------|
| No. | MM/DD/YY | DATE | BY | REVISION | Chk'd |
| 5 | 04/14/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 4 | 02/19/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 3 | 01/23/21 | KCL | | ISSUED FOR APPROVAL | KCL |
| 2 | 01/15/21 | KCL | | REVISED SITE GRADING | KCL |
| 1 | 01/12/21 | KCL | | REVISED SITE GRADING | KCL |


| | | | | | |
|-----|----------|------|----|----------------------|-------|
| No. | MM/DD/YY | DATE | BY | REVISION | Chk'd |
| 5 | 04/14/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 4 | 02/19/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 3 | 01/23/21 | KCL | | ISSUED FOR APPROVAL | KCL |
| 2 | 01/15/21 | KCL | | REVISED SITE GRADING | KCL |
| 1 | 01/12/21 | KCL | | REVISED SITE GRADING | KCL |

| | |
|--------|--|
| P.ENG. | |
| | |
| | |
| | |

| | |
|----------|------------|
| DRAWN | TWJM |
| DESIGN | TWJM |
| APPROVED | KCL |
| DATE | 2020.10.08 |
| SCALE | |
| HORIZ. | 1:750 |
| VERT. | N/A |


| | |
|---|-----------|
| PROTECH CONSULTING 2012 200 - 1461 St. Paul Street Kelowna, B.C. Phone 860-1771 FAX 860-1994 | |
| WESTBANK JOINT VENTURE SMITH CREEK STAGE 2 LOT LAYOUT | |
| DRAWING NO. | 20035-P01 |
| REV. NO. | 8 |

FILE LOCATION: P:\Projects\20035-0003 - Smith Creek Phase 2V - CAD FILES\3 - Preliminary Sheet Layout\3 - Preliminary Sheet Layout.dwg
DATE: 06/25/2021 2:51 PM
PLOTED:



NOT FOR
CONSTRUCTION


[illegible]



W. 1/2 D.L. 3478

FUTURE ROAD
FUTURE LOTS TO BE PRE SERVICED WITH SAN & STM
Plan KAP56155
ROAD STANDARD AS PER WEST KELOWNA STD. 200

PARK
Plan KAP57629



PRELIMINARY NOT FOR CONSTRUCTION

| LEGEND | |
|----------------|---------------|
| WATER | MANHOLE |
| SANITARY SEWER | POWER POLE |
| STORM SEWER | LAMP STANDARD |
| GAS | CATCH BASIN |
| UG TELEPHONE | HYDRANT |
| UG ELECTRICAL | TREES |

| No. | MM/DD/YY | BY | REVISION | Chk'd | No. | MM/DD/YY | BY | REVISION | Chk'd |
|-----|----------|------|---------------------|-------|-----|----------|------|-------------------------|-------|
| 4 | 06/25/21 | TWJM | ISSUED FOR APPROVAL | KCL | 3 | 06/10/21 | TWJM | ISSUED FOR COORDINATION | KCL |
| 2 | 05/25/21 | TWJM | ISSUED FOR APPROVAL | KCL | 2 | 05/25/21 | TWJM | ISSUED FOR APPROVAL | KCL |
| 1 | 04/14/21 | TWJM | ISSUED FOR APPROVAL | KCL | | | | | |




| | |
|----------|------------|
| DESIGNED | TWJM |
| APPROVED | KCL |
| DATE | 2021.02.24 |
| SCALE | 1:500 |
| HORIZ. | N/A |
| VERT. | N/A |


PROTECH CONSULTING 2012
200 - 1461 St. Paul Street Kelowna, B.C.
Phone 860-1771 FAX 860-1994

**WESTBANK JOINT VENTURE
SMITH CREEK STAGE 3
SITE SERVICING PLAN**


DRAWING NO. 20035-P05
REV. NO. 4




SECTION A-A




SECTION B-B




SECTION C-C




SECTION D-D




SECTION E-E



SECTION F-F



SECTION G-G




SECTION H-H

PRELIMINARY

NOT FOR
CONSTRUCTION

FILE LOCATION: P:\Projects\2020\20035 - Smith Creek Phase 2V - CIP FILES\3 - Preliminary Design\20035-P03-SIG-2000.dwg
PRINTED ON: 12/21/2021 1:53 PM

LEGEND
WATER
SANITARY SEWER
STORM SEWER
GAS
UG TELEPHONE
UG ELECTRICAL



MANHOLE
POWER POLE
LAMP STANDARD
CATCH BASIN
HYDRANT
TREES

○ MH
● P.P.
□ L.S.
▨ C.B.
● HYDRANT
● SERVICE BOX

I.C.
C.S.
LPT



No. MM/DD/YY DATE BY REVISION

Chk'd

No. MM/DD/YY DATE BY

REVISION

Chk'd



P.ENG.

DRAWN TWJM
DESIGN TWJM
APPROVED KCL
DATE 2020.10.22
SCALE
HORIZ. 1:1000
VERT. 1:200


PROTECH CONSULTING 2012
200 - 1461 St. Paul Street Kelowna, B.C.
Phone 860-1771 FAX 860-1994
WESTBANK JOINT VENTURE
SMITH CREEK STAGE 2
SITE GRADING CROSS SECTIONS

DRAWING NO.


REV. NO.

5


20035-P03




ASPEN PARK PLAN VIEW
SCALE 1:250




SECTION 1-1
SCALE 1:500




SECTION 2-2
SCALE 1:500



SECTION 3-3
SCALE 1:500



SECTION 4-4
SCALE 1:500



SECTION 5-5
SCALE 1:500

"RED LINED"

FILE LOCATION: P:\PROJECTS\2003\2003 - Smith Creek Phase 2V - CIP FILES\3 - Preliminary Design\2003-P10-ASPEN PARK SECTION.dwg
PRINTED ON: 12/20/21 11:53 AM

PRELIMINARY NOT FOR CONSTRUCTION

| LEGEND | |
|----------------|---------------|
| WATER | MANHOLE |
| SANITARY SEWER | POWER POLE |
| STORM SEWER | LAMP STANDARD |
| GAS | CATCH BASIN |
| UG TELEPHONE | HYDRANT |
| UG ELECTRICAL | TREES |

| No. | MM/DD/YY | DATE | BY | REVISION | CHK'd |
|-----|----------|------|----|-------------------------|-------|
| 3 | 06/25/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 2 | 05/25/21 | TWJM | | ISSUED FOR COORDINATION | KCL |
| 1 | 03/18/21 | KCL | | ISSUED FOR COORDINATION | KCL |




| |
|----------------|
| P.ENG. |
| DRAWN KCL |
| DESIGN KCL |
| APPROVED KCL |
| DATE MAR 2021 |
| SCALE AS NOTED |

| |
|----------------|
| DRAWN KCL |
| DESIGN KCL |
| APPROVED KCL |
| DATE MAR 2021 |
| SCALE AS NOTED |

PROTECH CONSULTING 2012
200 - 1461 St. Paul Street Kelowna, B.C. Phone 860-1771 FAX 860-1994


WESTBANK JOINT VENTURE
SMITH CREEK STAGE 2
ASPEN PARK CROSS SECTIONS

| | |
|-------------|-----------|
| DRAWING NO. | 20035-P16 |
| REV. NO. | 3 |



SIGHT LIMITATION ANALYSIS
CRITERIA STA 0+000 TO 0+120
STOPPING SIGHT DISTANCE = 30m (TAC TABLE 2.1.3.4 FOR 30KM/HR)
EYE HEIGHT = 1.05m
EYE OFFSET = 1.0m
TARGET HEIGHT = 0.6m
TARGET OFFSET = -1.0m

SIGHT LIMITATION ANALYSIS
CRITERIA STA 0+120 TO 0+530
STOPPING SIGHT DISTANCE = 65m (CWK BYLAW 0249 LOCAL ROAD)
EYE HEIGHT = 1.05m
EYE OFFSET = 1.0m
TARGET HEIGHT = 0.6m
TARGET OFFSET = -1.0m




PRELIMINARY

NOT FOR CONSTRUCTION

FILE LOCATION: P:\Projects\20035\20035 - Smith Creek Phase 2\1 - Civil Plans\1 - Preliminary Road Design\20035-P07-Plan-Profile.dwg
PRINTED ON: 1/25/2021 4:13 PM

| | | | | | |
|----------------|--|---------------|--|-------------|--|
| LEGEND | | | | | |
| WATER | | MANHOLE | | I.C. | |
| SANITARY SEWER | | POWER POLE | | C.S. | |
| STORM SEWER | | LAMP STANDARD | | LPT | |
| GAS | | CATCH BASIN | | SERVICE BOX | |
| UG TELEPHONE | | HYDRANT | | | |
| UG ELECTRICAL | | TREES | | | |

| No. | MM/DD/YY | DATE | BY | REVISION | Chk'd |
|-----|----------|------|----|---------------------|-------|
| 5 | 06/25/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 4 | 05/25/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 3 | 04/14/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 2 | 03/17/21 | KCL | | ISSUED FOR APPROVAL | KCL |
| 1 | 01/20/21 | BDK | | ISSUED FOR APPROVAL | KCL |





| | |
|----------|----------|
| P.ENG. | |
| DRAWN | BDK |
| DESIGN | KCL |
| APPROVED | KCL |
| DATE | JAN 2021 |
| SCALE | |
| HORIZ. | 1:500 |
| VERT. | 1:50 |

| | |
|----------|----------|
| DRAWN | BDK |
| DESIGN | KCL |
| APPROVED | KCL |
| DATE | JAN 2021 |
| SCALE | |
| HORIZ. | 1:500 |
| VERT. | 1:50 |

PROTECH CONSULTING 2012
200 - 1461 St. Paul Street Kelowna, B.C. Phone 860-1771 FAX 860-1994

WESTBANK JOINT VENTURE
SMITH CREEK STAGE 2
PRELIMINARY ROAD A PLAN/PROFILE



| | |
|-------------|-----------|
| DRAWING NO. | 20035-P07 |
| REV. NO. | 5 |



SIGHT LIMITATION ANALYSIS
CRITERIA STA 0+120 TO 0+530
STOPPING SIGHT DISTANCE = 65m (CWK BYLAW 0249 LOCAL ROAD)
EYE HEIGHT = 1.05m
EYE OFFSET = 1.0m
TARGET HEIGHT = 0.6m
TARGET OFFSET = -1.0m

PRELIMINARY

NOT FOR CONSTRUCTION



| LEGEND | |
|----------------|---------------|
| WATER | MANHOLE |
| SANITARY SEWER | POWER POLE |
| STORM SEWER | LAMP STANDARD |
| GAS | CATCH BASIN |
| UG TELEPHONE | HYDRANT |
| UG ELECTRICAL | TREES |

| No. | MM/DD/YY | DATE | BY | REVISION | CHK'd |
|-----|----------|------|----|---------------------|-------|
| 5 | 06/25/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 4 | 05/25/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 3 | 04/14/21 | TWJM | | ISSUED FOR APPROVAL | KCL |
| 2 | 03/17/21 | KCL | | ISSUED FOR APPROVAL | KCL |
| 1 | 01/20/25 | BDK | | ISSUED FOR APPROVAL | KCL |






| SCALE | HORIZ. | VERT. |
|-------|--------|-------|
| 1:500 | | |
| 1:50 | | |

PROTECH CONSULTING 2012
200 - 1461 St. Paul Street Kelowna, B.C.
Phone 860-1771 FAX 860-1094

WESTBANK JOINT VENTURE
SMITH CREEK STAGE 2
PRELIMINARY ROAD A PLAN/PROFILE 2

| DRAWING NO. | 20035-P08 |
|-------------|-----------|
| REV. NO. | 5 |



PRELIMINARY

NOT FOR CONSTRUCTION

FILE LOCATION: P:\Projects\2012\20035 - Smith Creek Phase 2V - Civil Files\3 - Preliminary Sheet Sample\1 - Preliminary Smith Creek Stage 2 P/P.dwg PLOT DATE: 06/25/2012 4:52 PM PRINTED

LEGEND

WATER

SANITARY SEWER

STORM SEWER

GAS

UG TELEPHONE

UG ELECTRICAL

MANHOLE

POWER POLE

LAMP STANDARD

CATCH BASIN

HYDRANT

TREES

○

●

□

⊞

●

MH

P.P.

L.S.

C.B.

I.C.

○

●

□

⊞

●

C.S.

LPT

SERVICE BOX

No.

MM/DD/YY

DATE

BY

REVISION

Chk'd

5

06/25/21

TWJM

ISSUED FOR APPROVAL

KCL

4

05/25/21

TWJM

ISSUED FOR APPROVAL

KCL

3

04/14/21

KCL

ISSUED FOR APPROVAL

KCL

2

03/17/21

KCL

ISSUED FOR APPROVAL

KCL

1

01/20/25

BDK

ISSUED FOR APPROVAL

KCL

WEST KELOWNA

P.ENG.

DRAWN

BDK

DESIGN

KCL

APPROVED

KCL

DATE

JAN 2021

SCALE

HORIZ. 1:500

VERT. 1:50

PROTECH CONSULTING 2012

200 - 1461 St. Paul Street Kelowna, B.C.

Phone 860-1771 FAX 860-1994

WESTBANK JOINT VENTURE

SMITH CREEK STAGE 2

PRELIMINARY SMITH CREEK ROAD P/P

DRAWING NO.

20035 -P11

REV. NO.

5

SILT FENCE NOTES:

- ALL DIMENSIONS ARE IN MILLIMETRES OR METRES UNLESS OTHERWISE SHOWN.
- FILTER FABRIC MAY BE A PERVIOUS SHEET OF SLIT FILM WOVEN POLYPROPYLENE, NYLON, POLYESTER, OR ETHYLENE YARN HAVING THE FOLLOWING MINIMUM CRITERIA:


| | |
|-------------------------|---|
| FILTERING EFFICIENCY | 90% |
| FLOW RATE | 0.012m ³ /m ² /minute |
| GRAB TENSILE STRENGTH | 700N |
| EQUIVALENT OPENING SIZE | 0.15mm |

- FILTER FABRIC MATERIAL MUST CONTAIN ULTRAVIOLET RAY INHIBITORS AND STABILIZERS TO PROVIDE A MINIMUM OF SIX MONTHS OF EXPECTED USABLE CONSTRUCTION LIFE AT TEMPERATURE RANGE OF -18°C TO 49°C (0°F TO 120°F)
- FILTER FABRIC MUST BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID USE OF JOINTS. WHEN JOINTS ARE NECESSARY, FILTER CLOTH MUST BE SPLICED TOGETHER ONLY AT SUPPORT POSTS.

MAINTENANCE:


- INSPECT IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. REPAIR AS NECESSARY
- SEDIMENT MUST BE REMOVED WHEN IT REACHES ONE HALF THE HEIGHT OF THE FENCE.
- ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE FILTER FENCE IS NO LONGER REQUIRED, MUST BE DRESSED TO CONFORM TO THE EXISTING GRADE, PREPARED, AND SEEDED.

Direction of flow →




NOTE:
A All dimensions are in millimetres or metres unless otherwise shown.

SILT FENCE DETAIL



SECTION VIEW






PLAN OF SILT FENCE BARRIER

■■■■■■■■■■ — SILT FENCE

USE OF COMPOST FILTER SOCK TO THE WEST OF THE INLET WITHIN THE DITCH TO FILTER RUNOFF PRIOR TO ENTERING THE STORM SYSTEM AS PER STD DWG SC-8-2

NOTE: Any additional access off the site will require the installation of an additional "Gravel Entrance"



PRELIMINARY

NOT FOR CONSTRUCTION

FILE LOCATION: P:\Projects\2013\20130303 - Smith Creek Phase 2V - Civil Plans\3 - Preliminary\Drawings\20130303-P12-030.dwg PLOTTED: 04/14/2013 1:18 PM

| | | | | | |
|----------------|---------|---------------|--------|-------------|-----|
| LEGEND | | | | | |
| WATER | —+—+—+— | MANHOLE | ○ MH | I.C. | —○— |
| SANITARY SEWER | —+—+—+— | POWER POLE | ● P.P. | C.S. | —●— |
| STORM SEWER | —+—+—+— | LAMP STANDARD | □ L.S. | LPT | —□— |
| GAS | —+—+—+— | CATCH BASIN | ■ C.B. | SERVICE BOX | —■— |
| UG TELEPHONE | —+—+—+— | HYDRANT | ● H | | |
| UG ELECTRICAL | —+—+—+— | TREES | ● T | | |

| | | | | | | | | | | | |
|-----|----------|------|----|----------|-------|-----|----------|------|---------------------|----------|-------|
| No. | MM/DD/YY | DATE | BY | REVISION | Chk'd | No. | MM/DD/YY | DATE | BY | REVISION | Chk'd |
| | | | | | | 3 | 06/25/21 | TWJM | ISSUED FOR APPROVAL | KCL | |
| | | | | | | 2 | 05/25/21 | TWJM | ISSUED FOR APPROVAL | KCL | |
| | | | | | | 1 | 01/23/21 | KCL | ISSUED FOR APPROVAL | KCL | |



PROTECH CONSULTING 2012
200 - 1461 St. Paul Street Kelowna, B.C.
Phone 860-1771 FAX 860-1994

WESTBANK JOINT VENTURE
SMITH CREEK STAGE 2
PRELIMINARY EROSION & SEDIMENT
CONTROL PLAN

DRAWING NO.
20035-P12
REV. NO.
3

SCALE
1:500

Schedule B


2802 SMITH CREEK ROAD, PHASE 2

Landscape Restoration Plan

DRAWING LIST

- L 1.0 Site Key, Notes, Legend + Plant List
- L 1.1 Area 1
- L 1.2 Area 2 + Area 3 + Area 4

Schedule 'B'



1 SITE RESTORATION KEY
L1.0 Not to scale

LANDSCAPE NOTES

- 1 | OKGN EHS Services Ltd. has been retained to be the qualified environmental professional and to function as the site inspector as it relates to the environment during construction.

2 | Plant material and construction methods shall conform to minimum standards established in the latest edition of the Canadian landscape standards, published by the C.N.L.A. and the C.S.L.A. as well as the City of West Kelowna landscape standards.

3 | The landscape design designated herein reflects the minimum City of West Kelowna guidelines.

4 | Final planting selections may vary depending upon availability at the time of construction. Substitutions to be reviewed and approved by project landscape designer prior to installation.

5 | Shrubs to be placed within planting pockets with adequate topsoil, minimum 0.45m (1.5') deep.
- 6 | To ensure plant survivability temporary irrigation to be installed and restoration area to be weeded for duration of maintenance period. Maintenance period is (3) years as per environmental report by OKGN EHS Services Ltd.

7 | All weeds to be removed by hand prior to planting.

8 | Native grass seed, to be grade "A" premium seed mix, placed on top of 100mm (4") imported growing medium. Multiple applications may be required for full establishment.

9 | Planting and hydroseed to occur in fall or spring weather windows (September - October, March -

April). Regardless of seasonal planting, temporary irrigation is required.

- 10 | Plant survivability is expected to be 50% at the end of the maintenance period. Re-planting at the end of each growing season is expected in order to meet this requirement.

PLANT LIST
SHRUBS

| QTY | BOTANICAL NAME | COMMON NAME | PLANT SIZE | SPACING |
|-----|-----------------------|--------------|------------|----------|
| 41 | Amelanchier alnifolia | Saskatoon | #1 Pot | As Shown |
| 27 | Ericameria nauseosa | Rabbitbush | #1 Pot | As Shown |
| 56 | Mahonia aquifolium | Oregon grape | #1 Pot | As Shown |
| 59 | Symphoricarpos albus | Snowberry | #1 Pot | As Shown |

| revision . issue | | |
|------------------|---------|-----|
| revised | July 14 | 04 |
| revised | June 22 | 03 |
| issued | Jan 24 | 02 |
| review | Jan 22 | 01 |
| DESCRIPTION | DATE | NO. |

| PROJECT |
|--|
| 2802 Smith Creek Kelowna BC |
| SHEET TITLE |
| Landscape Restoration Plan Cover Sheet |

| |
|------------------------|
| design by . Sarah Enns |
| project number . 21001 |
| date . July 14, 2021 |

| NORTH | SCALE as shown PAGE 24" x 36" |
|-------|--|
| | |

| SHEET NUMBER |
|--------------|
| L-1.0 |

REFER TO L-1.1 FOR NOTES AND PLANT LIST


LEGEND

- AMELANCHIER
- ERICAMERIA
- MAHONIA
- SYMPHOCARPUS
- NATIVE GRASS HYDROSEED
[SEE NOTES]

| revision . issue | | |
|------------------|---------|-----|
| revised | July 14 | 04 |
| revised | June 22 | 03 |
| issued | Jan 24 | 02 |
| review | Jan 22 | 01 |
| DESCRIPTION | DATE | NO. |

| PROJECT | |
|---|--|
| 2802 Smith Creek Kelowna BC | |
| SHEET TITLE | |
| Landscape Restoration Plan Area 1 | |

| |
|------------------------|
| design by . Sarah Enns |
| project number . 21001 |
| date . July 14, 2021 |




| | |
|---|-------------------|
| NORTH | SCALE as shown |
|  | PAGE 24" x 36" |

SHEET NUMBER

L-1.1

SCALE:
5 10 20 40m

REFER TO L-1.1 FOR NOTES AND PLANT LIST



LEGEND

- AMELANCHIER
- ERICAMERIA
- MAHONIA
- SYMPHOCARPUS
- NATIVE GRASS HYDROSEED [SEE NOTES]

revision . issue

| | | |
|-------------|---------|-----|
| revised | July 14 | 04 |
| revised | June 22 | 03 |
| issued | Jan 24 | 02 |
| review | Jan 22 | 01 |
| DESCRIPTION | DATE | NO. |

PROJECT

2802 Smith Creek
Kelowna BC

SHEET TITLE


Landscape
Restoration Plan
Area 1

design by . Sarah Enns

project number . 21001

date . July 14, 2021

NORTH



SCALE

as shown

PAGE

24" x 36"

SHEET NUMBER

L-1.2

Estimate of Probable Cost

Restoration Landscape Plan



PROJECT NAME | Smith Creek, Phase 2

PROJECT No. | 21008

DATE | June 22, 2021

| No. | ITEM | UNIT | QTY | COST | PRICE |
|-----|---|----------|------|-----------|----------|
| 1.0 | GROWING MEDIUM | | | | |
| 1.1 | Shrub growing medium, planting pocket 0.45m depth | m3 | 16 | \$20 | \$320 |
| 1.2 | Hydroseed growing medium, 0.10m depth | m3 | 713 | \$20 | \$14,260 |
| | | | | 1.0 TOTAL | \$14,580 |
| 2.0 | PLANT MATERIAL | | | | |
| 2.1 | Shrub - #1 pot | ea. | 183 | \$15 | \$2,745 |
| | | | | 2.0 TOTAL | \$2,745 |
| 3.0 | Hydroseed | | | | |
| 3.1 | Native, grade "A" premium, grass seed | m2 | 7133 | \$2 | \$10,700 |
| | | | | 3.0 TOTAL | \$10,700 |
| 4.0 | LABOUR | | | | |
| 4.1 | Professional monitoring | per year | 3 | \$525 | \$1,575 |
| 4.2 | Weed management plan | per year | 3 | \$1,200 | \$3,600 |
| | | | | 4.0 TOTAL | \$5,175 |
| | | | | TOTAL | \$33,200 |

Plus 25% \$8,300

NOTES:

1. See corresponding restoration drawings L-1.0 - L1.2 Issued June 22, 2021

Total Security: \$41,500

Schedule C

Westbank Joint Venture
c/o Bill Bonn
1109 Churchhill Road
Kelowna, BC
V1Y 8K9

July 13, 2021
File: 19254

Attention: Bill Bonn

**Re: Geotechnical Comments: Proposed Valley Stone Retaining Wall – Sunset Ranch Subdivision
Phase 2 – Copper Ridge Drive and Smith Creek, West Kelowna, BC**

We understand that a Valley Stone retaining wall is proposed at the above referenced site. The wall will span between Lots 17 and 19 and will be up to two tiers in height. The wall locations and heights are shown in the Smith Creek Stage 2 design drawings by Protech Consulting, dated June 25, 2021. The maximum wall heights will be 2.5 metres and the tiers will be separated by 2.0 metres (see Section F-F of Protech Drawing No. 20035-P03). We have also reviewed the wall design drawings provided by Basalite, dated June 2021, for this project which are attached to this letter. The drawings provide wall profiles, geogrid lengths, material specifications, cross-sections and other typical details which we expect are sufficient for your submission to the City of West Kelowna for Development Permit application. This letter is intended for the use of our client and their design team as well as the City of West Kelowna for use in the permitting process.

We have completed an analysis of the wall system including the geogrid reinforcement shown on the Basalite drawing, the wall geometry shown in the Protech drawings, and assuming compacted blast rock backfill within the geogrid zones. The results of our analysis indicate adequate factors of safety under both static and seismic conditions. Therefore, we are satisfied with the retaining wall design drawings attached to this letter. We are also satisfied with the location of the proposed retaining walls, as shown on the Protech drawings and we confirm there are no further setbacks required from a geotechnical perspective. We also confirm that these drawings are suitable for Development Permit submission for this project from a geotechnical perspective. GeoPacific will provide Issued for Construction drawings prior to the project proceeding to construction.

For:
GeoPacific Consultants Ltd.

Reviewed By:

Kevin Bodnar, M.Eng., P.Eng., P.E.
Principal

Albert Losch, P.Eng.
Senior Geotechnical Engineer

SMITH CREEK - STAGE 2 - LOTS 17-19

BASALITE WALL DESIGN PACKAGE

GENERAL DESIGN NOTES

1. The following effective strength design parameters were assumed in the preparation of structural calculations for the Basalite retaining wall system:

| | ϕ | c | γ (kN/m ³) |
|-----------------|--------|-----|-------------------------------|
| Reinforced Soil | 36° | 0 | 20 |
| Retained Soil | 36° | 0 | 20 |
| Foundation Soil | 36° | 0 | 20 |

Soil types and design properties shall be confirmed by the Owner or its geotechnical engineer prior to wall construction. Basalite accepts no responsibility for the interpretation or verification of subsurface conditions.

2. The system has been evaluated for internal stability and simple external sliding and overturning. Unless otherwise specified, the design maintains a minimum factor of safety of 1.5 on all elements of the wall design.

3. The walls are designed to support the following maximum surcharge loadings:

Live Load: 0 kPa
Dead Load: 100 kPa Line Load and 20 kPa
Backslope: 27 degrees

4. The wall foundation soils at each wall location shall be capable of safely supporting 150kN/m² (3000psf) or as indicated on the wall elevations without failure or excessive settlement. Local bearing capacity shall be confirmed by the site engineer.

5. The Contractor shall provide surface and subsurface drainage, grading, and erosion control during and after wall construction to avoid damage to the wall structure.

6. The Contractor is responsible for obtaining all permits and easements necessary for wall construction. The Contractor is responsible for protecting adjacent property from wall construction activities.

QUALITY ASSURANCE PROVISIONS

1. Wall construction shall be monitored by a qualified Engineer to verify field conditions. If this work is not performed by the site geotechnical engineer, the geotechnical engineer shall be consulted in those matters pertaining to soil conditions and wall performance.
2. The foundation soils at each wall location shall be inspected by the Engineer and any unsuitable soils or improperly compacted embankment material removed and replaced as directed by the Engineer prior to wall construction to provide adequate bearing capacity and minimize settlement.
3. All wall excavation and retained soils shall be inspected for groundwater conditions and any additional drainage provisions required in the field shall be incorporated into the wall construction as directed by the Engineer.
4. Wall backfill material shall be tested and approved by the Engineer for use in the reinforced soil zone meeting the minimum requirements of the approved design plans.
5. All soil backfill shall be tested by the Engineer for moisture, density, and compaction periodically (every geogrid layer) meeting the minimum requirements of the approved design plans or project specifications.
6. Wall construction shall be periodically inspected by the Engineer to ensure the geogrid reinforcement elevations and lengths are installed in accordance with the approved design plans.




FIGURE INDEX

| Description | Sheet No. |
|--------------------------|-----------|
| Title Sheet | 1 |
| Wall Elevations | 2 |
| Specifications | 3 |
| Valleystone Unit Details | 4 |
| | |
| | |
| | |

THIS DESIGN IS PRELIMINARY AND NOT FOR CONSTRUCTION UNLESS REVIEWED AND STAMPED BY A PROFESSIONAL ENGINEER




Title Page



Basalite Retaining Wall Systems
Typical Wall Details

June 2021



Figure 1



| SPECIFICATION GUIDELINES (Short Form) | | Basalite Specifications | | June 2021 | Figure 3 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|-----------|--|-----------|-----------|----------|------|--------|-------|------|--------|-----|--|--|--|--|------------|-----------|-------|-----|---------|--------|-------|-------|--------|-------|---------|-------|---------|-------|---------|-------|---------|------|----------|-----|
| THIS DESIGN IS PRELIMINARY AND NOT FOR CONSTRUCTION UNLESS REVIEWED AND STAMPED BY A PROFESSIONAL ENGINEER | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PART 1: GENERAL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1.01 DESCRIPTION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Work includes furnishing and installing a BASALITE retaining wall to the lines and grades shown on the construction drawings and as specified herein. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| B. Work includes preparing foundation soil, furnishing and installing leveling pad, unit fill and backfill to the lines and grades shown on the construction drawings. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C. Work includes furnishing and installing all related materials required for construction of the retaining wall as shown on the construction drawings. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1.02 REFERENCE STANDARDS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. ASTM C1372 Specification for Segmental Retaining Wall Units | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| B. ASTM D 422 Particle Size Analysis | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C. ASTM D 698 Laboratory Compaction Characteristics using Standard Effort. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D. ASTM D 4318 Liquid Limit, Plastic Limit, Plasticity Index of Soils | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| E. ASTM D 4595 Tensile Properties of Geotextiles - Wide Width Strip | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| F. ASTM D 5262 Unconfined Tension Creep Behavior of Geotextiles | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| G. NCMA SRWU-1 Test Method for Determining Connection Strength of SRW | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1.03 QUALITY ASSURANCE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Owner will be responsible for soil testing and inspection quality control during wall construction and earthwork operations. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PART 2: MATERIALS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.01 DEFINITIONS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Concrete Units - a BASALITE (Pro) modular concrete facing unit, machine made from portland cement, water and mineral aggregates. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| B. Structural Geogrid - a structural geogrid formed by a regular network of integrally connected tensile elements with apertures of sufficient size to allow interlocking with surrounding soil, rock, or earth and function primarily as reinforcement. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C. Unit Drainage Fill - drainage aggregate which is placed within and immediately behind the modular concrete units. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D. Reinforced Backfill - Compacted soil which is within the reinforced soil volume as shown on the plans. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.02 BASALITE UNITS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. BASALITE (Valleystone) wall units shall have a minimum 28-day compressive strength of 3,000 psi. Standard weight concrete shall have a maximum moisture absorption of 6% (6% in northern climates). | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.03 FIBERGLASS CONNECTING PINS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Connecting pins shall be 1/2" diameter thermoset isophthalic polyester resin pultruded fiberglass reinforcement rods supplied by the unit manufacturer. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.04 CONSTRUCTION ADHESIVE | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Material shall conform to ASTM 2339 and shall be supplied by the BASALITE unit supplier. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.05 GEOGRID REINFORCEMENT | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Geogrid shall be the type as shown on the drawings having the property requirements described within the manufacturer's specifications and required by the design calculations. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.06 BASE LEVELING PAD MATERIAL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Material shall consist of compacted crushed stone or unreinforced concrete as shown on the construction drawings. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.07 UNIT DRAINAGE FILL | | 2.08 REINFORCED BACKFILL | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Unit fill shall consist of clean 1" minus crushed stone or crushed gravel meeting the following gradation: | | A. Reinforced backfill shall be free of debris or organic material meeting the following gradation tested in accordance with ASTM D-422. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| <table><tr><th>Sieve Size</th><th>% Passing</th></tr><tr><td>1 inch</td><td>100</td></tr><tr><td>3/4"</td><td>75-100</td></tr><tr><td>No. 4</td><td>0-10</td></tr><tr><td>No. 50</td><td>0-5</td></tr></table> | | Sieve Size | % Passing | 1 inch | 100 | 3/4" | 75-100 | No. 4 | 0-10 | No. 50 | 0-5 | <table><tr><th>Sieve Size</th><th>% Passing</th></tr><tr><td>75 mm</td><td>100</td></tr><tr><td>37.5 mm</td><td>60-100</td></tr><tr><td>19 mm</td><td>35-60</td></tr><tr><td>9.5 mm</td><td>25-60</td></tr><tr><td>4.75 mm</td><td>20-40</td></tr><tr><td>2.36 mm</td><td>15-30</td></tr><tr><td>1.18 mm</td><td>10-20</td></tr><tr><td>0.30 mm</td><td>3-10</td></tr><tr><td>0.075 mm</td><td>0-8</td></tr></table> | | | | Sieve Size | % Passing | 75 mm | 100 | 37.5 mm | 60-100 | 19 mm | 35-60 | 9.5 mm | 25-60 | 4.75 mm | 20-40 | 2.36 mm | 15-30 | 1.18 mm | 10-20 | 0.30 mm | 3-10 | 0.075 mm | 0-8 |
| Sieve Size | % Passing | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1 inch | 100 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3/4" | 75-100 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| No. 4 | 0-10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| No. 50 | 0-5 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| Sieve Size | % Passing | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 75 mm | 100 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 37.5 mm | 60-100 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 19 mm | 35-60 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 9.5 mm | 25-60 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4.75 mm | 20-40 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.36 mm | 15-30 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 1.18 mm | 10-20 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 0.30 mm | 3-10 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 0.075 mm | 0-8 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Material can be site excavated material when the above requirements are met. Unsuitable soils for backfill (high plastic clays or organic materials) shall not be used in the reinforced soil mass. | | C. Contractor shall submit reinforced fill sample and test results to the Architect/Engineer for approval prior to construction. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 2.09 DRAINAGE PIPE | | 2.10 GEOTEXTILE FILTER FABRIC | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. When required, drainage pipe shall be perforated or slotted PVC pipe manufactured in accordance with ASTM F794 and F949 equivalent to A-2000 Perforated Pipe by Contech Construction Products. | | A. When required, geotextile filter fabric shall be a 4.0 oz/sy, polypropylene, needle punched nonwoven fabric equivalent to C45NW. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| PART 3: EXECUTION | | 3.01 EXCAVATION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Contractor shall excavate to the lines and grades shown on the construction drawings. Contractor shall be careful not to disturb embankment and foundation materials beyond lines shown. | | 3.02 FOUNDATION SOIL PREPARATION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Foundation soil shall be excavated as required for leveling pad dimensions shown on the construction drawings, or as directed by the Engineer. | | B. Unsuitable soils shall be removed and replaced with approved compacted material as directed by the Engineer | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C. Over-excavated areas shall be backfilled with approved compacted backfill material. | | 3.03 BASE LEVELING PAD | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Leveling pad materials shall be placed upon an approved foundation as shown on the construction drawings to a minimum thickness of 150 mm (6"). | | B. Aggregate material shall be compacted to provide a dense, level surface on which to place the first course of modular units. Compaction shall be to 95% of Modified Proctor Density as determined in accordance with ASTM D1557. For crushed rock, material shall be densely compacted as determined by visual observation. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 3.04 UNIT INSTALLATION | | 3.05 GEOGRID INSTALLATION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. The first course of concrete modular wall units shall be carefully placed on the base leveling pad. Each unit shall be checked for level and alignment. | | A. Geogrid shall be laid at the proper elevations and orientation as shown on the construction drawings or as directed by the Engineer. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| B. Units are placed side by side for full length of wall alignment. Alignment may be done by means of a string line or offset from a base line. | | B. Correct orientation (roll direction) of the geogrid shall be verified by the contractor with the strongest direction placed perpendicular to the wall. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C. Install fiberglass connecting pins and fill all voids in and around the modular units with unit fill material. Tamp or rod unit fill to insure that all voids are completely filled. | | C. Geogrid soil reinforcement shall be connected to the BASALITE wall units by placing the geogrid over fiberglass pins and laying the grid back on compacted fill. Place the next course of units over the geogrid. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| D. Sweep excess material from top of units and install the next course. Ensure that each course is completely unit filled, backfilled and compacted prior to proceeding to next course. | | D. The geogrid shall be pulled taut to eliminate loose folds and pretension the reinforcement. Stake or secure back edge of geogrid prior to and during backfill and compaction. Geogrid shall be placed side by side with no gaps. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| E. Place each subsequent course ensuring that pins protrude into adjoining courses a minimum of 1". Two pins are required per unit. Pull each unit forward, away from the fill zone, locking against the pins in the previous course and backfill as the course is completed. Repeat procedure to the extent of wall height. | | 3.06 FILL PLACEMENT | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Backfill material shall be placed in 300 mm (12") lifts and compacted to 95% of Modified Proctor density as determined in accordance with ASTM D1557. The in-place moisture content shall not exceed the optimum moisture content as determined in accordance with ASTM D1557 and be no lower than 3% below optimum moisture content | | B. Backfill shall be placed, spread and compacted in such a manner that minimizes the development of slack or loss of pretension of the geogrid. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| C. Only hand-operated compaction equipment shall be allowed within 3' of the back surface of the BASALITE units. | | D. Backfill shall be placed from the wall back towards the embankment to ensure that the geogrid remains taut. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| E. Tracked construction equipment shall not be operated directly on the geogrid. A minimum backfill thickness of 6" is required prior to operation of tracked vehicles over the geogrid. Turning of tracked vehicles should be kept to a minimum to prevent tracks from displacing the fill and damaging the geogrid. | | F. Rubber-tired equipment may pass over the geogrid reinforcement at slow speeds, [less than 10 mph.] Avoid sudden braking and sharp turning. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| G. At the end of each day's operation, the Contractor shall grade the backfill away from the wall and direct runoff away from the wall face. The Contractor shall not allow surface runoff from adjacent areas to enter the wall construction site. | | 3.07 CAP INSTALLATION | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| A. Place BASALITE Cap units over projecting pins from units below. Apply adhesive to top surface of unit below and place cap unit into position. Backfill and compact to finished grade with low permeability soil. | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |



Schedule D



LEGEND

PROPERTY LINE

EXISTING SETBACK LINE

PROPOSED SETBACK LINE

PROPERTIES INCLUDED IN THE VARIANCE APPLICATION

VARIANCE TO FRONT PARCEL SETBACK 6.0m TO **3.5 m**

VARIANCE TO FRONT PARCEL SETBACK 6.0m TO 4.5m

LEGEND

MANHOLE

POWER POLE

LAMP STANDARD

CATCH BASIN

HYDRANT

TREES

○ MH

○ P.P.

□ L.S.

■ C.B.

● SERVICE BOX

I.C.

C.S.

LPT

SERVICE BOX

No.

MM/DD/YY

DATE

BY

REVISION

Chk'd

No.

MM/DD/YY

DATE

BY

REVISION

Chk'd

WEST KELOWNA

P.ENG.

DRAWN KCL

DESIGN KCL

APPROVED KCL

DATE JUNE 2021

SCALE HORIZ. 1:300 VERT. N/A

PROTECH CONSULTING 2012

200 - 1461 St. Paul Street Kelowna, B.C.

Phone 860-1771 FAX 860-1994

WESTBANK JOINT VENTURE

SMITH CREEK STAGE 2

DEVELOPMENT VARIANCE PLAN

DRAWING NO. 20035-P19

REV. NO. 2